# CITY OF LODI

PUBLIC WORKS DEPARTMENT

## Sidewalk and Driveway with Planting Strip

Notes:

1. Alternate "A" shall be used, except where the driveway slope approaches 3 inches per foot. It may then be necessary to use Alternate "B".
2. When Alternate "B" is used sidewalk shall be removed to nearest score–mark by sawing. When the sidewalk is replaced the existing scoring pattern shall be maintained.
3. Additional compaction is not required where existing curb and gutter, sidewalk, and/or driveway are being removed and replaced.
4. Class B concrete per Section 90 of Std. Specs, 1–1/2" max. aggregate with impervious membrane cure and light broom finish.



| Dr. K | No. | Date | Revision | Appr. |
|---|---|---|---|---|
| | 1 | 9/03 | ADDED SCORE LINES | |
| Ch. WS | 2 | 2/04 | ADDED FILL AREA IN PARKWAY | |
| | 3 | 2/05 | REVISED PAGE 1 | |
| Date 12/00 | | | | |

Approved By: F. Wally Sandelin
F. Wally Sandelin
City Engineer
R.C.E. 39895

2/2/05
Date

STD PLAN
121